

Vibration Tests for ECAL Mission Success

SERMS @Terni (Italy), Nov./Dec. 2003



Involved Institutions

ECAL Group:

- INFN Pisa
 M. Incagli, F. Pilo, S. Di Falco,
 S. Giurgola
- · LAPP
 - C. Adloff, F. Cadoux,
 - G. Cougoulat, J.M. Dubois,
 - N. Fouque, L. Journet,
 - D. Fougeron, R. Kossakowski,
 - S. Rosier, J. Tassan
- MITY. Wang







Hosted by:

- INFN Perugia
 R. Batiston, Bruna Bertucci
- Perugia University
 L. Di Masso
- SERMS
 S. Ascani, D. Cosson, G. Scolieri







Participants





Plan

- Previous tests
- Vibration test at SERMS-Terni
- · Accelerometers results
- PMTs results
- · Conclusion



Previous Tests

- BISEE (Beijing, China, January 2003):
 ECAL Structure
 - -> 1rst eigen frequency in agreement with FEM
 - -> SQ tests of ECAL Structure passed
- ESIA (Annecy, France, February 2003):
 Light collecting system + PMT+ EFE
 - -> no damage observed for 3 PMTs tested up to $6 q_{RMS}$



SERMS at Terni



SERMS

Laboratorio per lo Studio degli

Effetti delle Radiazioni sui

Materiali per lo Spazio



- SERMS shaker capability:
 - up to 3.4 g_{RMS} for 2000 kg
 - maximum weight of 950 kg in vertical position
- · Under the supervision of Simone Ascani



Goals

X, Y and Z vibrations:


- Sine sweep to check eigen resonances (10Hz-500Hz)
- Random spectrum (10Hz-2000Hz):


X @ 3.1 g_{RMS}

Y @ 2.3 g_{RMS}

Z @ 3.2 g_{RMS}

(NASA specifications)





One side of ECAL equipped: 2 * 5 (PMTs +EFE) connected to 2 EIBs


(ECAL fully equipped: 324 PMTs - 36 EIBs)

LEDs on the side opposite to the equipped PMT side

1 radiator covers PMT side



Sequence of the Tests




First period: Nov. 17 - Nov. 21 Second period: Dec. 3 - Dec 5


- PMTs Acq.
 before
- Sine sweep before
- Random
- Sine sweep after
- PMTs Acq. after



X and Y Vibrations










Preparation for Z vibrations



Weight constraints:

Elastic rope Shaker load < 950 kg

ECAL = 650 kg USS-02 = 110 kg

Intermediary supports = 430 kg (China)

120 kg (Italy)

1310 kg

360 kg are removed with the help of a crane + an elastic rope.



Preparation for Z vibrations





10 days delay!



ECAL Meeting, CERN, January 08, 2004




Z vibrations






Z Vibrations





Z vibrations





Accelerometers installed


quantity	situation	type
3	Back panel	triaxial
1	EIB	triaxial
1	Honeycomb	triaxial
2	Radiator	triaxial
4	USS-02	standard
6	Honeycomb	miniature

Control




Accelerometers installed

22-23-24





25-26-27

28-29-30



19-20-21









Accelerometers installed

34-35-36





31-32-33










X and Y Vibrations


X axis studies (Before and after "Random")

- Radiator winglets and radiator centre - C 36 C 33






X and Y Vibrations





Z vibrations





Accelerometers study

From sine sweep vibration tests:


- ·no change of eigen resonances after random
- ·1rst mode for X-Y vibration: 89 Hz
- ·1rst mode for Z vibration: 62 Hz
- -> confirm China vibration tests

At end of all test:

Bolt torsion moment checked: ok



PMT acquisition




The overall reproductibility of the system better than 10%

Catherine Adloff ECAL Meeting, CERN, January 08, 2004



PMT acquisition

- PMT HV @ 680 V
- several amplitudes for LED signals
- Provisional readout:
 - Intermediate board specially built to match EIB with BDR
 - BDR board



For Z vibrations: upgrade of power supply distribution



PMT acquisition

- · ECAL equipped with 10 PMTs
 - -> 40 anode signals
 10 dynode signals
- 10 acquisitions for each PMT
- Each acquisition:
 11 steps of light intensity (30 evts/step)




Results

For all PMTs:

Pedestals are stable

No change in the answer to the LED light within 5 to 10 %.


Example: PMT 9- Anode 4 gain 1 2.3 g_{RMS} ©3.1g_{RMS} @3.2 @ @ >>××N Before
After
After
Before
After
After
After






Checks back to LAPP

- · Standard acquisition (see previous slide): ok
- All PMT HV up to 900 V (PMT specified max. HV): ok



PMT 5 Annode 2 gain 1




PMT 6 Annode 2 gain 1



Checks back to LAPP

- Block PMTs dismounted:
 - check optical couplers from scratches: ok
 - check light cones: ok





Conclusion

Vibration tests of ECAL + PMTs successfully completed at SERMS - Terni.

- -> measurements confirm 1rst modes found during China vibration tests
- -> No damage for light collecting systems, PMTs, electronics (B1,B2,EFE,EIB)

This validates the vibration part of the ECAL mission success tests.