#### Nationaal Lucht- en Ruimtevaartlaboratorium

National Aerospace Laboratory NLR













## **AMS Tracker Thermal Control Subsystem**

## **TTCB EMI/EMC Test Report**

AMSTR-NLR-TRP-008 Issue 1.0 June 2009

Sun Yat-Sen University (SYSU)
National Aerospace Laboratory (NLR)
Instituto Nazionale di Fisica Nucelare (INFN)

	NAME	ORGANISATION/RESPONSIBILITY	SIGNATURE	DATE
PREPARED	J. van Es/Z. Zhang	NLR		
CHECKED	J. van Es	NLR / AMS SE		
AGREED	A. Pauw	NLR / AMS PA		
APPROVED	J. van Es	NLR / AMS PM		
AUTHORISED	P. Dieleman	NLR Space Department		

FILENAME	AMSTR-NLR-TEMP-001_1.0work_Document_Template.doc	ORDER-/CODENUMBER:	2494047
LAST SAVED	2009.06.30 13:08 by J. van Es	DIVISION:	AS&A
PRINTED	2009.06.30 18:44	DISTRIBUTION:	Unlimited
PAGES	51	CLASSIFICATION TITLE:	Unclassified





Page Doc.Id Issue

Date

**2** of 51 AMSTR-NLR-TR-008

June 2009

1.0

#### TTCB EMI/EMC Test Report

#### **Distribution list**

Company	FOR*	Name	Comments
SYSU	ı	Z.H. He	
		X. Qi	
		T. Li	
INFN	ı	R. Battiston	
		M. Menichelli	
		C. Gargiulo	
		A. Alvino	
		E. Laudi	
AMS	I	M. Capell	
		V. Koutsenko	
		R. Becker	
NLR	I	P. Dieleman	
		J.van Es	
		M. Bardet	
Jacobs Sverdrup	I	C. Tutt	
		G. Clark	
CGS	I	M. Molina	
		C. Vettore	

A = Approval R = Review

I = Input / Information

An electronic version of this document is available on the AMS TTCS website: https://ams-ttcs.nlr.nl





Doc.ld

Page

**3** of 51 **AMSTR-NLR-TR-008** 

Issue Date

**1.0** June 2009

#### TTCB EMI/EMC Test Report

**Document change log** 

 $\underline{Change\ Ref.}\qquad \underline{Section(s)}$ 

<u>Issue 1.0</u>

All

Initial issue





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

AMSTR-NLR-TR-008

June 2009

**4** of 51

1.0

#### **Summary**

This report shows the test results of the EMI/EMC testing of the TTCB-P box.

The tests were performed at the CEM laboratory in Terni Italy. The test was supported by NLR, INFN and SYSU.

All TTCB and TTCE radiated emission are below the requirement levels.

TTCB/TTCE survived the EMC test campaign. No degradation in functional behaviour was found after the test.

However the TTCB/TTCE set-up showed to be susceptible to both horizontal and vertical H-fields (200 MHz-1 GHz).

The following anomalies take place in the H-field:

- 1. Pump speed increase upto approximately additional 3500 rpm
- 2. Probable a communication problem resulting in pump switch off
- 3. Pt1000 increase with max 4 degrees °C
- 4. DS increase of maximum 2.5 °C. Especially spare DS (not attached to any construction) are susceptible (DS14 & DS16).
- 5. APS noise





Page Doc.ld Issue

Date

**5** of 51 AMSTR-NLR-TR-008

1.0 June 2009

## TTCB EMI/EMC Test Report

## Contents

Do	ocument o	change log	3
Su	mmary		4
1	Scope o	f the document	7
2	Referen	aces documents	7
3	Test Se	t-up description	8
4	Hardwa	are under test	8
5	Test Pr	ogramme	9
	5.1	Part A: EMI radiation emission tests (performed on June 10)	9
	5.2	Source of interference during zero-field reference measurements	10
	5.3	Part B: EMC interference measurements	11
6	Test fac	cility/equipment description	13
	6.1	TTCB Safety	14
	6.2	Test set-up picture	15
7	Part A:	EMI radiation emission results	21
	7.1	Frequency: A~F Test results	22
8	Part B:	EMC Test results	24
	8.1	Frequency: Spike 1, Spike 2 and G	25
9	Freque	ncy: H-horizontal	27
	9.1	H-horizontal TTCE-B pump speed 3500 rpm	29
	9.2	H-horizontal TTCE-B pump speed 6000 rpm	30
	9.3	H-horizontal TTCE-B pump speed 10,000 rpm	31
	9.4	H-horizontal TTCE-A pump speed 3500 rpm	32
	9.5	H-horizontal TTCE-A pump speed 6000 rpm	33
	96	H-horizontal TTCF-A nump speed 10 000 rpm	34





Page Doc.ld 6 of 51 AMSTR-NLR-TR-008

1.0

Issue

TTCB EMI/EMC Test Report Date June 2009

10	Frequency:	: H-vertical	35
	10.1	H-vertical TTCE-A pump speed 3500 rpm	37
	10.2	H-vertical TTCE-A pump speed 6000 rpm	38
	10.3	H-vertical TTCE-A pump speed 10,000 rpm	41
	10.4	H-vertical TTCE-A pump speed 6,000 rpm (repeated)	42
	10.5	H-vertical TTCE-B pump speed 3500 rpm and 6000 rpm	43
	10.6	H-vertical TTCE-B pump speed 10,000 rpm	44
	Frequency:		45 47
13	Conclusion	ıs	49
	13.1	EMI test results	49
	13.2	XXX test results	49
	13.3	How to proceed Error! Bookma	rk not defined
EN	D OF DOC	UMENT	51

(51 pages in total)





Doc.Id Issue

**7** of 51 AMSTR-NLR-TR-008

Date

Page

June 2009

1.0

#### TTCB EMI/EMC Test Report

#### Scope of the document

The document shows the (functional) test data performed during the tests. Additional information to this test report can be found in the filled procedure sheets of

#### 2 References documents

Ref	Title	Number
RD-1	TTCB EMC EMI procedure	AMSTR-NLR-PR-029
RD-2	TTCB EMC EMI procedure Part B	AMSTR-NLR-PR-029





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

**8** of 51 **AMSTR-NLR-TR-008** 

1.0

June 2009

#### 3 Test Set-up description

#### 4 Hardware under test

The TTCB-p flight module. The TTCB was operational during EMC/EMI test and therefore connected to Ground Support Equipment to form a closed loop filled with CO2. The GSE-loop will be equipped with a mass flow meter, absolute pressure transducer, differential pressure transducer and temperature sensors.





Page Doc.Id Issue  $\label{eq:sof51} \mbox{9 of 51}$   $\mbox{AMSTR-NLR-TR-008}$ 

1.0

TTCB EMI/EMC Test Report

Date June 2009

#### 5 Test Programme

#### 5.1 Part A: EMI radiation emission tests (performed on June 10)

During the emissivity test the following actuator will be switched on to measure the emission. If possible the actuators will be switched on separately, no other actuators active or as less as possible.

	Actuator	Pump running	comment
1	Peltier elements	no	PWM, 10 %
2	Accumulator heater FAC	no	PWM, 90 % (TBC)
3	TTCB pump	yes	3500, 6000, 10000 RPM
4	Pre-heater	yes (minimal flow)	Manual ON/OFF (2s/10s)
5	Start Up Heater	yes (minimal flow)	Manual ON/OFF (2s/10s)
6	Cold Orbit Heater	yes (minimal flow)	Manual ON/OFF (2s/10s)

<b>Test Abbrevation</b>	Test name and Frequency range					
	Б	2009-06-				
	Day 1	10				
	Radiated Emission Test			14 KHz	15.5 GHz	
	Radiated Linission Test			IXIIZ	OHZ	
Α	KHz	14	150	KHz		
В	KHz	150	30	MHz		
C (Hor)	MHz	30	300	MHz	POL H	
C (Ver)	MHz	30	300	MHz	POL V	
D (Hor)	MHz	300	700	MHz	POL H	
D (Ver)	MHz	300	700	MHz	POL V	
E (Hor)	GHz	700	1	GHz	POL H	
E (Ver)	GHz	700	1	GHz	POL V	
F (Hor)	GHz	1	15.5	GHz	POL H	
F (Ver)	GHz	1	15.5	GHz	POL V	





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

10 of 51
AMSTR-NLR-TR-008

June 2009

#### 5.2 Source of interference during zero-field reference measurements

During the zero-field test prior to testing three sources of interference were found:

- 1. CAN-controller connection. With the Can-box grounded and a linear power supply the problem was solved.
- 2. NI DAC unit was also interfering. This was solved by changing the power supply. The thermal bath was also producing interfering fields. This was solved to switch the bath off during the susceptible EMI test.

During the EMI test it was found that in most case the pump did not induce any EMI problem. Therefore the pump was ran in more cases then stated in section 5.1 and heaters could be operated during longer times.




Figure 5-1: Can controller grounding on EMC chamber ground





TTCB EMI/EMC Test Report

Page Doc.ld Issue **11** of 51 **AMSTR-NLR-TR-008** 

1.0

Date June 2009

#### **5.3** Part B: EMC interference measurements

GHz

GHz

O (Hor)

O (Ver)

The EMC/EMI overall test sequence is:

Test Abbrevation	Test name and Frequency range						
	Day 1 2009-06-10						
	Radiated Emis	sion Test		14 KHz	15.5 GHz		
Α	KHz	14		KHz			
В	KHz	150		MHz			
C (Hor)	MHz	30		MHz	POL H		
C (Ver)	MHz	30		MHz	POL V		
D (Hor)	MHz	300		MHz	POL H		
D (Ver)	MHz	300		MHz	POL V		
E (Hor)	GHz	700		GHz	POL H		
E (Ver)	GHz	700	1	GHz	POL V		
F (Hor)	GHz	1	15.5	GHz	POL H		
F (Ver)	GHz	1	15.5	GHz	POL V		
	Day 2	2009-06-11					
	Radiated Spike	es	(RS-02)				
				minutes	# TTCB CONF		
Spike 1	pulses		10 micro	1	13		
Spike 2			150 nano	1	13		
	Radiated	Electric field	level	(RS03)			
G	Khz	14	10	Mhz			
H (Hor)	MHz	200		GHz	POL H		
H (Ver)	MHz	200		GHz	POL V		
I (Hor)	GHz	1	2	GHz	POL H		
I (Ver)	GHz	1		GHz	POL V		
J (Hor)	GHz	2		GHz	POL H		
J (Ver)	GHz	2		GHz	POL V		
K (Hor)	GHz	4		GHz	POL H		
K (Ver)	GHz	4	8	GHz	POL V		
L (Hor)	GHz	8		GHz	POL H		
L (Ver)	GHz	8	10	GHz	POL V		
M (Hor)	GHz	2.2		GHz	POL H		
M (Ver)	GHz	2.2		GHz	POL V		
N (Hor)	GHz	8.5		GHz	POL H		
N (Ver)	GHz	8.5		GHz	POL V		
0 (11 )	1						

13.7

13.7

15.2 GHz

15.2 GHz

POL V





TTCB EMI/EMC Test Report

Page Doc.ld

AMSTR-NLR-TR-008

NIK-NLK-IK-UU

Issue Date

June 2009

1.0

**12** of 51

The main test steps of Part B (to be performed on June 11 and June 12) are:

- 1. Operate TTCB and conduct EMC/EMI test
- 2. Perform pre-test Health check (see sheets) TTCE-A & TTCE-B
- 3. Perform Spike 1 Test
  - a. TTCE-A
    - i. Pump operation test 3500 rpm & FAC on automatic control
    - ii. Pump operation 6000 rpm & TEC on (10% duty cycle)
    - iii. Pump operation 10,000 rpm & FAC on automatic control
    - iv. Perform health check on Pt1000's and DS during all operation (logged)
  - b. TTCE-B
    - i. Pump operation test 3500 rpm & FAC on automatic control
    - ii. Pump operation 6000 rpm & TEC on (10% duty cycle)
    - iii. Pump operation 10,000 rpm & FAC on automatic control
  - c. Perform health check on Pt1000's and DS during all operation (logged)
- 4. Perform Spike 2 Test
  - a. TTCE-B
    - i. Pump operation test 3500 rpm & FAC on automatic control
    - ii. Pump operation 6000 rpm & TEC on (10% duty cycle)
    - iii. Pump operation 10,000 rpm & FAC on automatic control
    - iv. Perform health check on Pt1000's and DS during all operation (logged)
  - b. TTCE-A
    - i. Pump operation test 3500 rpm & FAC on automatic control
    - ii. Pump operation 6000 rpm & TEC on (10% duty cycle)
    - iii. Pump operation 10,000 rpm & FAC on automatic control
  - c. Perform health check on Pt1000's and DS during all operation (logged)
- 5. Perform test G
- 6. Perform test H (Hor) (after anomaly highest rpm was lowered to 8000 rpm)
- 7. Perform test H (Ver)
- 8. .....
- 9. Perform test O (Hor)
- 10. Perform test O (Ver)
- 11. Empty TTCB
- 12. Disconnect TTCB from TCCE
- 13. Transport TTCE to TV-chamber for TTCB-S TV testing

All tests were done for TTCE-A and TTCE-B in order ABBAABBAABB etc.





Issue

AMSTR-NLR-TR-008

ue

Page

Doc.ld

Date

June 2009

**13** of 51

#### TTCB EMI/EMC Test Report

#### 6 Test facility/equipment description

The test is performed at SERMS (Terni) at the EMC/EMI test facility and the following type of equipment will be used for operating the TTCB:

- TTCE / cables / CAN-if / pc with TTCE sw
- CO2
- Mass flow meter
- Absolute transducer
- Differential pressure transducer
- Temperature sensors, TC type T
- NI cDAQ system
- Pc with LV sw
- Thermostat bath for cooling CO2 (GSE-loop)




Figure 6-1: schematic with GSE for operating TTCB

As the EMI/EMC air conditioners could not keep the temperature below 20 °C. Therefore the TTCB box is put in a plastic temperature controlled volume inside the EMI/EMC chamber. This to provide a temperature below 20 °C during testing (by a portable air conditioner). Apart from the EMI testing the portable air conditioner could be used during all tests.





Page Doc.ld Issue

Date

**14** of 51 **AMSTR-NLR-TR-008** 

June 2009

1.0

TTCB EMI/EMC Test Report




Figure 6-2: TTCB schematic with additional tubing for functional test

#### **6.1 TTCB Safety**

To avoid over pressurising of the TTCB and moreover the valves and the connectors a safety relief valve is put in the system. This safety relieve valve will open at 69 bar which is approximately a CO2 two-phase saturation temperature of +29 °C. During the night the air conditioners of the EMI chamber were put al full power to keep the TTCB below +29 °C.





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

 $\begin{tabular}{l} \textbf{15} of 51 \\ \textbf{AMSTR-NLR-TR-008} \end{tabular}$ 

June 2009

1.0

#### **6.2** Test set-up picture

In the below pictures the test set-up is shown.



Figure 6-3: Air conditioned set-up in the CEM EMC chamber (table grounding)



Figure 6-4: Air conditioned set-up in the CEM EMC chamber (cabling connection)





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

16 of 51

AMSTR-NLR-TR-008

1.0

June 2009



Figure 6-5: Air conditioned set-up in the CEM EMC chamber (TTCE next to TTCB)



Figure 6-6: Cooling loop set-up outside the chamber





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

 $\label{eq:first} \mbox{17 of 51} \\ \mbox{AMSTR-NLR-TR-008}$ 

June 2009

1.0




Figure 6-7: Cooling loop set-up outside the chamber detail




Figure 6-8: Power supply set-up outside the chamber during test run





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

**18** of 51 **AMSTR-NLR-TR-008** 

June 2009

1.0




Figure 6-9: Detail front side TTCB-P test set-up




Figure 6-10: NI DAC system detail





TTCB EMI/EMC Test Report

Page
Doc.ld A

Date

**19** of 51 **AMSTR-NLR-TR-008** 

**1.0** June 2009



Figure 6-11: Item under test TTCB-P front side




Figure 6-12: Item under test TTCB-P back side





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

 $\label{eq:condition} \textbf{20} \text{ of 51} \\ \textbf{AMSTR-NLR-TR-008} \\$ 

1.0

June 2009



Figure 6-13: Item under test TTCB-P connectors





TTCB EMI/EMC Test Report

Doc.ld Issue

Page

**21** of 51 **AMSTR-NLR-TR-008** 

1.0

Date June 2009

#### 7 Part A: EMI radiation emission results

All the TTCB components showed to fulfil the EMI test requirements.

Test Abbrevation	Test name and Frequency range						
	Day 1	2009-06- Day 1 10					
	Radiated Emission Test			14 KHz	15.5 GHz		
A	KHz	14	150	KHz			
В	KHz	150	30	MHz			
C (Hor)	MHz	30	300	MHz	POL H		
C (Ver)	MHz	30	300	MHz	POL V		
D (Hor)	MHz	300	700	MHz	POL H		
D (Ver)	MHz	300	700	MHz	POL V		
E (Hor)	GHz	700	1	GHz	POL H		
E (Ver)	GHz	700	1	GHz	POL V		
F (Hor)	GHz	1	15.5	GHz	POL H		
F (Ver)	GHz	1	15.5	GHz	POL V		

The induced filed are shown in RD-3 (TBC).

All the below shown actuators induced fields are checked in for the separate frequencies.

	Actuator	Pump running	comment
1	Peltier elements	no	PWM, 10 %
2	Accumulator heater FAC	no	PWM, 90 % (TBC)
3	TTCB pump	yes	3500, 6000, 10000 RPM
4	Pre-heater	yes (normal flow)	Manual ON during complete
			EMI test duration
5	Start Up Heater	yes (normal flow)	Manual ON during complete
			EMI test duration
6	Cold Orbit Heater	yes (normal flow)	Manual ON during complete
			EMI test duration

The function check test results are shown in below figures.






Page 22 of 51
Doc.Id. AMSTR-NLR-TR-008
Issue 1.0

June 2009

Date

TTCB EMI/EMC Test Report

#### 7.1 Frequency: A~F Test results



PT1000, Pump speed and APS







**23** of 51 Page Doc.ld. AMSTR-NLR-TR-008 1.0 Issue June 2009

Date

TTCB EMI/EMC Test Report

25 -Frequency: A~F DS 24 23 DS4BP DS10BP 22 DS11BP DS14BP DS7BP 21 DS8BP Temp/°C DS1BP DS12BP DS15BP DS9BP DS13BP -DS3BP DS2BP 18 DS16BP DS5BP DS6BP 17 16 15 12:00 13:00 14:00 15:00 16:00 17:00 19:00 18:00 Time

#### Dallas sensors







 Page
 24 of 51

 Doc.Id.
 AMSTR-NLR-TR-008

 Issue
 1.0

 Date
 June 2009

TTCB EMI/EMC Test Report

#### 8 Part B: EMC Test results

In the below section he (functional) test results during the EMC field testing are shown. Only in the horizontal and vertical H-field (200 mHz-1 GHz) anomalies were found in the TTCB/TTCE operation and communication. In the rest of the fields the TTCB/TTCE operated without any problems.

Day 2 2009-06-11

	Radiated Spikes	(RS-02)		
			minutes	# TTCB CONF
Spike 1	pulses	10 micro	1	13
Spike 2		150 nano	1	13

	Radiated	Electric field	level	(RS03)	
G	Khz	14	10	Mhz	
H (Hor)	MHz	200	1	GHz	POL H
H (Ver)	MHz	200	1	GHz	POL V
I (Hor)	GHz	1	2	GHz	POL H
I (Ver)	GHz	1	2	GHz	POL V
J (Hor)	GHz	2	4	GHz	POL H
J (Ver)	GHz	2	4	GHz	POL V
K (Hor)	GHz	4	8	GHz	POL H
K (Ver)	GHz	4		GHz	POL V
L (Hor)	GHz	8	10	GHz	POL H
L (Ver)	GHz	8	10	GHz	POL V
M (Hor)	GHz	2.2		GHz	POL H
M (Ver)	GHz	2.2		GHz	POL V
N (Hor)	GHz	8.5		GHz	POL H
N (Ver)	GHz	8.5		GHz	POL V
O (Hor)	GHz	13.7	15.2	GHz	POL H
O (Ver)	GHz	13.7	15.2	GHz	POL V







 Page
 25 of 51


 Doc.Id.
 AMSTR-NLR-TR-008

 Issue
 1.0

 Date
 June 2009

TTCB EMI/EMC Test Report

#### 8.1 Frequency: Spike 1, Spike 2 and G



PT1000, Pump speed and APS







Page 26 of 51


Doc.Id. AMSTR-NLR-TR-008

Issue 1.0

Date June 2009

TTCB EMI/EMC Test Report

#### Dallas sensors









Page 27 of 51

Doc.Id. AMSTR-NLR-TR-008


Issue 1.0

Date June 2009

TTCB EMI/EMC Test Report

## 9 Frequency: H-horizontal

#### H-horizontal-overview









 Page
 28 of 51


 Doc.Id.
 AMSTR-NLR-TR-008

 Issue
 1.0

 Date
 June 2009

TTCB EMI/EMC Test Report

#### H-horizontal-overview Dallas Sensors








Page Doc.ld Issue **29** of 51 **AMSTR-NLR-TR-008** 


ISTR-NLR-TR-008 1.0

TTCB EMI/EMC Test Report


Date June 2009

#### 9.1 H-horizontal TTCE-B pump speed 3500 rpm





200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ







TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date


**30** of 51 **AMSTR-NLR-TR-008** 

June 2009


1.0

#### 9.2 H-horizontal TTCE-B pump speed 6000 rpm

PT1000, Dallas\_B, APS, RPM







200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ





Page Doc.ld  $\mathbf{31} \text{ of 51}$   $\mathbf{AMSTR\text{-}NLR\text{-}TR\text{-}008}$ 

Issue Date


June 2009

1.0


TTCB EMI/EMC Test Report

#### 9.3 H-horizontal TTCE-B pump speed 10,000 rpm

PT1000, Dallas\_B, APS, RPM



200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ



200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ



RPM P

Temp/°C

12



## AMS Tracker Thermal Control Subsystem

Page Doc.ld Issue **32** of 51

AMSTR-NLR-TR-008


TTCB EMI/EMC Test Report


Date

June 2009

1.0

## $9.4 \ H\hbox{-horizontal TTCE-A pump speed 3500 rpm}$





Time






Page Doc.ld Issue **33** of 51 **AMSTR-NLR-TR-008** 


1.0

TTCB EMI/EMC Test Report


Date June 2009

#### 9.5 H-horizontal TTCE-A pump speed 6000 rpm





#### 200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ



200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ





TTCB EMI/EMC Test Report

Doc.Id

Date

Page


**34** of 51 AMSTR-NLR-TR-008


Issue

June 2009


1.0

#### 9.6 H-horizontal TTCE-A pump speed 10,000 rpm





#### 200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ



200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽

# AMS Tracker Thermal Control Subsystem TTCB EMI/EMC Test Report

 Page
 35 of 51


 Doc.Id.
 AMSTR-NLR-TR-008

 Issue
 1.0

Date June 2009

### 10 Frequency: H-vertical

## H-vertical-overview




TTCB EMI/EMC Test Report

Page **36** of 51

Doc.Id. **AMSTR-NLR-TR-008**Issue **1.0** 

Date June 2009

#### H-vertical overview Dallas Sensors







TTCB EMI/EMC Test Report

Page Doc.ld Issue


Date


 $\begin{tabular}{ll} \bf 37 \ of \ 51 \\ \begin{tabular}{ll} \bf AMSTR-NLR-TR-008 \\ \end{tabular}$ 

**1.0** June 2009

### 10.1 H-vertical TTCE-A pump speed 3500 rpm







200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ

- Increase of Pt1 to 28 C while pressure is still according to 26 C.
- Increase in pump speed with 3000 rpm
- Dallas sensor information to be added





TTCB EMI/EMC Test Report

Page Doc.Id

Date

**38** of 51

AMSTR-NLR-TR-008


Issue

June 2009


1.0

### 10.2 H-vertical TTCE-A pump speed 6000 rpm

PT1000, APS, RPM and Dallas sensors



200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ



200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ

- Sudden stop in DS read-out
- Communication failure \*\*\* err = 0x110A \*\*\* resulting in pump switch off
- Increase of pump speed (248 MHz & 475 MHz)





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

AMSTR-NLR-TR-008

1.0

**39** of 51

June 2009

- APS increase but outside APS showed normal values (248 & 475 MHz)
- Pt1000 increase on all Pt1000's

The Dallas sensor read-out stopped during the test.

```
Jun 11 15:28:11 2009: +16.38 +16.56 +16.81 +16.69 +19.94 +18.62 +16.81 +17.00 +17.25
+18.00 + 18.44 + 20.62 + 16.50 + 20.81 + 16.69 + 20.00 + 15.88 + 15.69 + 0.00 + 0.00 + 0.00 + 0.00
+0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00
+0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00
+0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00
+0.00 +0.00 +0.00
Thu Jun 11 15:28:16 2009: +16.38 +16.56 +16.81 Thu Jun 11 15:31:15 2009: +16.75 +17.25
+16.75 +18.56 +20.25 +18.62 +17.06 +16.88 +18.50 +18.12 +18.69 +20.56 +17.19 +20.75
+17.00 + 20.38 + 16.88 + 16.69 + 0.00 + 0.00 + 0.00 + 0.00 + 0.00 + 0.00 + 0.00 + 0.00 + 0.00
+0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00
+0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00
+0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00
Thu Jun 11 15:31:21 2009: +16.75 +17.31 +16.75 +18.62 +20.25 +18.62 +17.00 +16.88
+18.50 +18.12 +18.62 +20.62 +17.19 +20.75 +16.94 +20.31 +16.94 +16.69 +0.00 +0.00
+0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00
+0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00
+0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00
+0.00 +0.00 +0.00 +0.00 +0.00
Thu Jun 11 15:31:26 2009: +16.75 +17.31 +16.75 +18.69 +20.25 +18.62 +17.00 +16.88
+18.50 +18.06 +18.50 +20.62 +17.25 +20.81 +16.88 +20.19 +16.94 +16.75 +0.00 +0.00
+0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00
+0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00 +0.00
+0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00 \ +0.00
+0.00 +0.00 +0.00 +0.00 +0.00
```





TTCB EMI/EMC Test Report

The following data problem was shown just before the moment the pump stopped operating:

Page Doc.ld Issue

Date

**40** of 51 **AMSTR-NLR-TR-008** 

June 2009

1.0

```
6.1\ 86.7\ 0.0\ 0.6+23.12+16.25+25.88+18.25+16.94+97.69+98.38+97.31+97.75+98.44
+97.31 +97.75 +97.75 +97.81 +97.75 +97.75 +97.75 +98.44 +97.31 +97.75 +98.44 +97.31
2009.06.11\ 15:29:25\ *** err = 0x110A\ ***
2009.06.11 15:29:26 *** err = 0x110A ***
2009.06.11\ 15:29:27\ *** err = 0x110A\ ***
2009.06.11\ 15:29:28\ *** err = 0x110A\ ***
2009.06.11\ 15:29:29\ *** err = 0x110A\ ***
2009.06.11 15:29:30 *** err = 0x110A ***
2009.06.11\ 15:29:31\ *** err = 0x110A\ ***
2009.06.11\ 15:29:32\ *** err = 0x110A\ ***
2009.06.11\ 15:29:33\ *** err = 0x110A\ ***
2009.06.11\ 15:29:34\ *** err = 0x110A\ ***
2009.06.11\ 15:29:35\ *** err = 0x110A\ ***
2009.06.11\ 15:29:36\ *** err = 0x110A\ ***
2009.06.11\ 15:29:37\ *** err = 0x110A\ ***
2009.06.11\ 15:29:38\ *** err = 0x110A\ ***
2009.06.11\ 15:29:39\ *** err = 0x110A\ ***
2009.06.11 15:29:40 *** err = 0x110A ***
2009.06.11 15:29:41 *** err = 0x110A ***
2009.06.11\ 15:29:42\ *** err = 0x110A\ ***
2009.06.11\ 15:29:43\ *** err = 0x110A\ ***
2009.06.11 15:29:44 *** err = 0x110A ***
2009.06.11\ 15:29:45\ *** err = 0x110A\ ***
2009.06.11\ 15:29:46\ *** err = 0x110A\ ***
2009.06.11 15:29:47 *** err = 0x110A ***
2009.06.11\ 15:29:48\ *** err = 0x110A\ ***
2009.06.11\ 15:29:49\ *** err = 0x110A\ ***
5.8 1.7 0.0 0.2 +23.31 +16.69 +21.62 +18.25 +17.62 +97.81 +97.19 +97.31 +97.88 +97.19
```

+97.31 +97.31 +97.31 +97.31 +97.31 +97.31 +97.81 +97.19 +97.31 +97.81 +97.19 +97.31





Doc.ld Issue

Page

AMSTR-NLR-TR-008

1.0


**41** of 51

TTCB EMI/EMC Test Report

Date June 2009

### 10.3 H-vertical TTCE-A pump speed 10,000 rpm

PT1000, APS, RPM and Dallas sensors



- Pump speed increase and APS noise
- Missing data is an import failure into figures don't pay attention (will be solved)
- DS sensor susceptibility leading to T-increase





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date


AMSTR-NLR-TR-008

**1.0** June 2009


**42** of 51

### 10.4 H-vertical TTCE-A pump speed 6,000 rpm (repeated)

PT1000, APS, RPM and Dallas sensors







200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ

- Increase of pump speed, the pump stop is not repeated
- APS noise
- DS output not affected





TTCB EMI/EMC Test Report

Doc.Id Issue

Page


**43** of 51

AMSTR-NLR-TR-008 1.0


Date June 2009

### 10.5 H-vertical TTCE-B pump speed 3500 rpm and 6000 rpm

PT1000, APS, RPM and Dallas sensors



200MHZv 300MHZv 400MHZv 500MHZv 600MHZv 700MHZv 800MHZv 900MHZv 1GHZ 200MHZv 300MHZv 400MHZv 500MHZv 600MHZv 700MHZv 800MHZv 1GHZ



#### Remarks:

Pump speed variations, Pt1000 variations, APS noise, no DS anomalies





Doc.ld Issue

Page

AMSTR-NLR-TR-008

**44** of 51


AMSTR-NLR-TR-008

TTCB EMI/EMC Test Report


Date June 2009

### 10.6 H-vertical TTCE-B pump speed 10,000 rpm

PT1000, APS, RPM and Dallas sensors



200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ



200MHZ₽ 300MHZ₽ 400MHZ₽ 500MHZ₽ 600MHZ₽ 700MHZ₽ 800MHZ₽ 900MHZ₽ 1GHZ

- Communication failure during for rpm>10,000
- Manual switched off pump





TTCB EMI/EMC Test Report

 Page
 45 of 51


 Doc.Id.
 AMSTR-NLR-TR-008

 Issue
 1.0

 Date
 June 2009

### 11 Frequency: I J M K L

### PT1000, Pump speed and APS







TTCB EMI/EMC Test Report


 Page
 46 of 51

 Doc.Id.
 AMSTR-NLR-TR-008

 Issue
 1.0

Date June 2009

### Dallas sensors



The hick-up in the data is missing data due to a missing file. This is not due to the EM-field but a file storage failure.





TTCB EMI/EMC Test Report


Page **47** of 51

Doc.ld. **AMSTR-NLR-TR-008**Issue **1.0** 

Date June 2009

# 12 Frequency: N, O.

### PT1000, Pump speed and APS



Dallas sensor data






Doc.Id. AMSTR-NLR-TR-008
Issue 1.0

Page

**48** of 51

June 2009

TTCB EMI/EMC Test Report Date







TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

AMSTR-NLR-TR-008

1.0

**49** of 51

June 2009

#### 13 Conclusions

Overall the TTCB survived the EMI-EMC test campaign. No degradation in functional behaviour was found after the test.

#### 13.1 EMI test results

All TTCB and TTCE radiated emission are below the requirement levels.

#### 13.2 EMS Interference test results

However the TTCB/TTCE set-up showed to be susceptible to both horizontal and vertical H-fields (200 MHz-1 GHz).

The following anomalies take place:

- 1. Pump speed increase upto approximately 3500 rpm
- 2. Pt1000 increase with max 4 degrees °C
- 3. DS increase of maximum 2.5 °C. Especially spare DS (not attached to any construction) are susceptible (DS14 & DS16).
- 4. APS noise
- 5. A possible communication problem was found resulting in switch off of the pump (not reproducible)

The pump susceptibility was also found during the pump EMI/EMC testing. It was decided not to shield the pump as additional flow does not have major impact on the Tracker temperature.

The Pt1000 sensor T-variations (especially) specifically Pt1 and Pt2 will impact Tracker temperature stability. The Tracker will go up and down with the variation in Pt1 and the cavitation health guard will be impacted by variations in Pt2.

The impact of Dallas sensor and APS susceptibility is less severe as these are only used form monitoring purposes.

A "communication" error occurred during the test resulting in system and pump switch off.

Most likely cause of the susceptibility and "communication" error is the lack of cable shielding between TTCE and TTCB or shielding of TTCB internal cabling.





TTCB EMI/EMC Test Report

Page Doc.ld Issue

Date

 ${f 50}~{
m of}~{f 51}$  AMSTR-NLR-TR-008

1.0

June 2009

### 13.3 Proposed next steps

In order to check if cable shielding will solve the problem H-field test with TTCE could be done to discriminate between TTCE-TTCB cabling shielding or internal box shielding of Pt1000- DS and actuator sensor.

Based on that information it can be decided if cable shielding is a possible solution to the susceptibility.

The pump speed susceptibility was also detected during pump testing. It is not needed to shield the pump as it has no influence on operation.

The communication S/W error should be investigated on order to understand what caused the system shut down.





TTCB EMI/EMC Test Report

 Page
 51 of 51

 Doc.Id
 AMSTR-NLR-TR-008

 Issue
 1.0

Date June 2009

# **END OF DOCUMENT**