






# Alpha Magnetic Spectrometer (AMS) - 02 Critical Design Review Structural Testing & Cyromagnet System Testing Flow







Phil Mott May 13-16, 2003

# Non-Linear Cryomagnet Support Straps Verification Testing


- Cryomagnet Support System Static Testing (England & US)
  - All strap components will have multiple tests to failure (completed)
  - All strap components will have multiple fatigue tests (completed)
  - 2 complete strap assemblies tested for fatigue & failure
    - Static test to 1.0 x limit load to characterize the strap (completed)
    - Fatigue tested includes transportation, launch, on-orbit, landing (completed)
    - Another static test to 1.0 x limit load to compare to pre-fatigue static test (completed)
    - Straps will then be dynamically tested (see dynamic test section) (completed)
    - Following all previous testing, straps will be static tested to failure
      - Warm test at JSC STL J13
      - Cold test at CTG in England
  - Each STA & Flight strap will be tested to 1.2 x limit load



- Flight Cryomagnet Static Testing (England)
  - The Flight Cryomagnet will be tested to 1.1 x limit load due to magnetic forces
  - Each coil is tested to at least full current.
    - Strain gages are attached to 1 dipole coil and 1 racetrack coil for FEM correlation.



- Component Level Static Tests
  - –Strap Static Test (JSC STL J13)
    - Test to 1.2 \* Maximum Flight Load & check for yielding
    - Repeat Test to Failure






- Component Level Static Tests (cont.)
  - VC Joint Stiffness Static Test (JSC STL J13)
    - With and without liquid shim in joint clearance holes
    - Test each configuration to failure
    - Measure stiffness of each bolted joint for FEM correlation

**Support Ring Simulator Plate** 

**Conical Flange Simulator Plate** 




**Anti-Rotation Load Cells** 

**Load Cell / Actuator** 



- Component Level Static Tests (cont.)
  - O-Ring Test Fixture Static Test (JSC STL J13)
    - Positive Pressure (0.8 atm gauge)
    - Help correlate FEM









- Component Level Static Tests (cont.)
  - Interface Plate Static Test (JSC STL J13)
    - Lower USS-02 Joint to VC Interface Plate (low margin and analysis uncertainty)
      - Flight Interface Plate with Lower Joint Simulator
      - Test to 1.1 x limit and check for yielding
      - Repeat test to failure
  - Lower Joint Static Test (JSC STL J13)
    - Lower USS-02 Joint (low margin)
      - Flight Lower Joint
      - Test to 1.1 x limit and check for yielding
      - Repeat test to failure







### **Lower Joint Static Test**





- PAS Static Test (LM3 Completed February 2003)
  - –ISS Configuration
  - -Static tested to 1.5 x limit load to ensure that it will meet the required stiffness and deflection requirements








# **Static Verification Testing**

- Full Assembly Static Test (JSC STL J13)
  - Orbiter Configuration simulated with modified test stands from AMS-01 on STS-91
  - -Test to 1.1 x limit load
  - Will include enough instrumentation to correlate FEM to 1.4 x
     limit load



# **Static Verification Testing**








- Acoustic Tests
  - Cryomagnet System (ESTEC The Netherlands)
    - Cryomagnet Structural Test Article (STA) [STA VC, STA SFHe Tank,
       Cold Mass Replica] will be tested to flight acoustic levels to determine if there is any o-ring seal leakage
    - Test must be performed with cryosystem at room temperature and vacuum in order to measure leaks in the o-ring seals
    - Strap preload increased to simulate thermal load of Cold Mass Replica










- Dynamic Tests
  - -Cryomagnet Support System (Straps) (LM Denver)
    - 2 complete strap assemblies were dynamically tested to determine dynamic and damping characteristics
    - Included enough instrumentation to dynamically correlate FEM of 1 DOF model









- Dynamic Tests (cont.)
  - –Cryomagnet System Sine Sweep Tests (INFN)
    - Cryomagnet STA (STA VC, STA SFHe Tank, Cold Mass Replica)
      will be tested in a sine sweep test in order to excite the non-linear
      support straps to load levels so that the strap reaches and
      extends into the stiffness region associated with the launch strap
      engagement
    - Input environment will be developed using non-linear DCLA results. The Cryomagnet system response will be analytically determined and reproduced during testing.
    - Test will be performed with the system at cryogenic temperatures
    - Will include enough instrumentation to dynamically correlate FEM (Discussed during the Dynamics Presentation)




**STA Cryosystem in the Vacuum Case Test Fixture (VCTF)** 








phil.mott@Imco.com / trent.martin@Imco.com





- Modal Tests
  - -Full Assembly Modal Test (JSC STL J13)
    - Orbiter Configuration simulated with modified test stands from AMS-01 on STS-91
    - Test will be performed with the system at cryogenic temperatures
    - Will include enough instrumentation to dynamically correlate FEM







- O-Ring Test Fixture (JSC STL Tests On-Going)
  - Sub-scale vacuum vessel will be used to show that the leak rate through the o-ring seals is at an acceptable level
  - Used to develop vacuum leak check procedures for the STA & Flight Vacuum Case
  - First vacuum pull was instrumented to aid in FEM correlation








- -Vacuum Case
  - Both the Flight & STA VC will undergo proof pressure testing to 1.0 x MDP (0.8 atm gauge). The STA will be proof tested twice. (This is an emergency case only because the system is designed for normal use as a vacuum vessel and not as a pressure vessel.)
  - Both the Flight & STA VC will undergo vacuum leak checks at various stages during the static and dynamic testing.


Vacuum leak checks at various stages of assembly and at final

assembly.





- -Cryomagnet Pressure Systems
  - SFHe Tank Proof Pressure Tests to 1.1 x MDP
  - Plumbing Systems Proof Pressure Tests to at least 1.5 x MDP
  - Warm He Tank Proof Pressure Test to at least 1.5 x MDP
  - He Leak Tests Throughout assembly and final assembly
  - Small Scale Dewar Vent Tests (Successfully Completed)
    - Safety Panel agrees that testing proved no Shuttle overboard vent will be required (See minutes "ams2tim011703")









- -TRD & TCS Pressure Systems
  - TRD Xe Tank
    - Proof Pressure Test to 1.5 x MDP
    - Random Vibration to 8.9 Grms Exceeds AMS-02 requirements
    - Same as tank used in Plasma Contactor Unit (PCU) built by Arde
  - TRD CO<sub>2</sub> Tank
    - Proof Pressure Test to 1.5 x MDP
    - Random Vibration to 8.9 Grms (axial) & 4.5 Grms (lateral) Exceeds
       AMS-02 requirements
    - Also built by Arde
  - TCS CO<sub>2</sub> Tank
    - Proof Pressure Test to 1.5 x MDP
  - Plumbing Systems
    - Proof Pressure Tests to at least 1.5 x MDP
  - Warm Helium Tank to Operate Cryosystem Warm Valves
    - Proof Pressure Test to at least 1.5 x MDP




# **Cyromagnet System Testing Flow**






### JSC / U.S.



- Proof Pressure Test
- Vacuum Leak Check
- Perform Small Scale O-ring Leak Testing
- Perform Small Scale pressure testing
- Weld tests

### ETH, SCL, HBE



- Proof Pressure Test
- He Leak Check

**CMR** w/ STA SFHe Tank

Cryomagnet STA

### SCL, England

- Initial Assembly & Welding
- Proof Pressure Test
- Vacuum Leak Check


### England/JSC/LM Denver

- Perform Strap Static/Dynamic/ Thermal/Fatigue Testing





### INFN, Italy



- Sine Sweep Test
- Vacuum Leak Checks during testing
- **Begin Long Duration** Vacuum Leak Tests

### **England**

- Small Dewar **Vent Tests** 



Cryomagnet


# ESTEC, Netherlands








Phil Mott / Trent Martin








### **JSC**



 Continue long duration endurance and leak checks

Cryomagnet STA


### JSC / U.S.



- Proof Pressure Test
- Vacuum Leak Check

Flight VC

### ETH / SCL / HBE




- He Tank Proof Pressure Test
- He Tank He Leak Check

Magnet

### LOCKHEED MARTII


### **AMS Collaboration**



- -Experiment Components
- -Sub-component Testing

Integrate Payload in Switzerland

### SCL, England



- Flight VC & Magnet
- Proof Pressure Test
- Vacuum Leak Check
- Magnetic Load Static Testing
- Quench Testing



